



QUOTE

Advance Insulation Canada

PO BOX 48158 RPO Uptown
Victoria, BC V8Z 7H6
TF: 855-531-3626
D: 778-229-4739
info@advanceinsulation.ca

DATE: 01/05/2026
QUOTE # 15621
BILL TO: Richard Fremmerlid
1517 San Juan Ave
Victoria, BC
(250) 885-7003

Insulation Services at 1517 San Juan Ave, Victoria, BC

DESCRIPTION	AMOUNT
Mobe and demobe crew and equipment to site	
Attic Space	
Set up floor coverings and necessary hoardings	
Hoardings will start at the front door and follow all foot traffic paths	
Extract attic insulation in entire attic space total 1680 SF with extractor vacuum disposing product into extraction bags	
Remove existing baffles at eaves	
Install new Cora vent baffles at the eaves (doubles) in every truss opening X80	
Install fiberglass batt insulation directly below the baffles to add value and act as an insulation stop for the blow-in insulation	
Seal and tape all breaches in the vapour barrier (to the best ability)	
<i>Note: The existing vapour barrier is 3ml, it is thin and has a vast amount of tears and breaches</i>	
<i>AIC recommends the use of spray foam insulation on the attic floor as per quote# 15620</i>	
Install low expansion foam on all ceiling to attic penetrations and air seal	
Install vapour boots on all light penetrations and air seal	
Install new vapour boots above bathroom fan base (attic side) and air seal	
Remove and replace existing bathroom fan ducting with new 4" flex duct with insulated wrap	
Seal, tape and attach at base	
Connect to roof exhaust vent (supplied and installed by others)	
Install ROXUL insulation around kitchen range hood vent	
Install fiberglass batt insulation below lower intake vents	

DESCRIPTION	AMOUNT
Build up attic hatch framing to 18" with conventional lumber	
Install 6" rigid foam on hatch lid	
Install R28 batt insulation above attic hatch	
Install new weather-stripping on hatch lid	
Check and inspect all woodwork inside attic to make sure it is suitable for re-installation	
Install new blow-in insulation in entire attic space to R50 blow-in insulation total 1680 SF (product to be used OC Pro Pink)	
Full site clean up of work area	
<i>AIC will not be held liable for any ventilation issues re intake/outtake that may arise in the future</i>	
Recommendations:	
<i>Certified Roofer to inspect all roof surfaces and report to client</i>	
<i>Certified Roofer to inspect roof for ventilation and report to client</i>	
Disclaimer We warrant our product for a term of one year from date of completion. This includes, only the installation of our product and we are not responsible for any faulty workmanship of other companies involved or previously involved in the building/renovation of your property. We guarantee our product and the install of our product and ensure every precaution is taken to ensure no issues arise in the future. We are not liable for roof leaks, plugged roof vents, faulty interior attic penetrations, air leakage from house to attic space, natural disasters or major influxes in temperature causing unforeseen damages. Full terms and conditions can be viewed at www.advanceinsulation.ca	
Quote is valid for 30 days	SUBTOTAL \$9,532.00
Please be advised that while working in confined attic spaces, damage to existing drywall on the ceilings below may occur. This is an unavoidable occurrence of working in attics over finished areas. If any damage is to arise from this work, AIC will provide a written quote to repair the damages. AIC is not to be held accountable for these damages, should they occur.	TAX RATE 5.00%
	SALES TAX \$ 476.60
Make all cheques payable to Advance Insulation Canada.	TOTAL \$ 10,008.60
	
GST #773780085RT0001	WCB# 075381